



Town of Allenstown
Town Administrator
16 School St.
Allenstown, NH 03275
603-485-4276 ext. 112
smulholland@allenstownnh.gov

CHANGE ORDER #2

River Rd. Paving & Reconstruction Project 2016 Phase II

The contract is changed as follows by adding the additional work as detailed below;

Budget numbers for continuation of paving on River Road.

Starting from end of new work at Granite Street intersection to beginning of guard rail at brook crossing approximately 2500 feet.

1.5 inch shim and overlay of 1815' x 25' Total of 5,042 square yards.

Estimated 431 tons @ \$63.50 per TON Total \$27,368.50

Reclaim and grade area 600' x 24' Total 1,840 square yards

1,840 square yards @ \$1.60 per SY Total \$2,944.00

Removal of excess reclaim by Highway Department

Paving of reclaimed area with 2 inch binder course and 1 inch wearing course.

Estimated 315 tons @ \$63.50 per TON Total \$20,002.50

Hand work paving

Estimated 12 tons @ \$125.00 per TON Total \$1,500.00

Milling of end joints and driveways

Total \$800.00

TOTAL WORK ESTIMATE

\$52,615.00

The Total project cost is approved to be increased by an amount not to exceed \$52,615. Contractor will be reimbursed for the amount of actual units used as described above. All other provisions of the original contract remain in effect as originally agreed to. This document serves as an amendment to the original contract.

Approved by:

Date:

Shaun Mulholland
Town Administrator