



The State of New Hampshire  
**Department of Environmental Services**



**Robert R. Scott, Commissioner**

**WETLANDS AND NON-SITE SPECIFIC PERMIT 2020-01405**

**NOTE CONDITIONS**

**PERMITTEE:** NH DEPT OF TRANSPORTATION  
C/O ANDREW O'SULLIVAN  
PO BOX 483  
CONCORD NH 03302

**PROJECT LOCATION:** ROUTE 28 RIGHT OF WAY, ALLENSTOWN  
TAX MAP #ROW, LOT #ROW

**WATERBODY:** SUNCOOK RIVER

**APPROVAL DATE:** AUGUST 07, 2020

**EXPIRATION DATE:** AUGUST 07, 2025

Based upon review of the above referenced application, in accordance with RSA 482-A and RSA 485-A:17, a Wetlands Permit and Non-Site Specific Permit was issued by the New Hampshire Department of Environmental Services (NHDES). This permit shall not be considered valid unless signed as specified below.

**PERMIT DESCRIPTION:** Dredge and fill 6,887 square feet within the bed and banks of the Suncook River (impacting 276 linear feet) for rehabilitation of NHDOT Bridge No. 107/098 (NH RTE 28) including replacement of bridge superstructure, deck, and wingwalls with rip rap placement along the southern abutment slope and two piers. Temporarily impact 5,907 square feet of bed and banks of the Suncook River (154 linear feet) for construction access and for installing erosion and dewatering controls.

**THIS APPROVAL IS SUBJECT TO THE FOLLOWING PROJECT SPECIFIC CONDITIONS:**

1. In accordance with Env-Wt 307.16, all work shall be done in accordance with the plans for NHDOT for Federal Aid Project No. X-A004(369), State Project No. 40362, NH Route 28 in Allenstown-Pembroke plans dated June 5, 2020 as received by the NH Department of Environmental Services (NHDES) on June 19, 2020.
2. In accordance with Env-Wt 307.07, all development activities associated with any project shall be conducted in compliance with applicable requirements of RSA 483-B and Env-Wq 1400 during and after construction.
3. In accordance with Env-Wt 307.03(a), no activity shall be conducted in such a way as to cause or contribute to any violation of surface water quality standards specified in RSA 485-A:8 or Env-Wq 1700; ambient groundwater quality standards established under RSA 485-C; limitations on activities in a sanitary protective area established under Env-Dw 302.10 or Env-Dw 305.10; or any provision of RSA 485-A, Env-Wq 1000, RSA 483-B, or Env-Wq 1400 that protects water quality.
4. All work shall be conducted and maintained in such a way as to protect water quality as required by Rule Env-Wt 307.03(a) through (h).
5. In accordance with Env-Wt 307.03(c)(4), water quality control measures shall be capable of minimizing erosion; collecting sediment and suspended and floating materials; and filtering fine sediment.
6. In accordance with Env-Wt 307.03(c)(3), water quality control measures shall be installed prior to start of work and in accordance with the manufacturer's recommended specifications or, if none, the applicable requirements of Env-Wq 1506 or Env-Wq 1508.

[www.des.nh.gov](http://www.des.nh.gov)

29 Hazen Drive • PO Box 95 • Concord, NH 03302-0095  
NHDES Main Line: (603) 271-3503 • Subsurface Fax: (603) 271-6683 • Wetlands Fax: (603) 271-6588  
TDD Access: Relay NH 1 (800) 735-2964

7. In accordance with Env-Wt 307.03(c)(5), water quality control measures shall be maintained so as to ensure continued effectiveness in minimizing erosion and retaining sediment on-site during and after construction.
8. In accordance with Env-Wt 307.03(c)(6), water quality control measures shall remain in place until all disturbed surfaces are stabilized to a condition in which soils on the site will not experience accelerated or unnatural erosion by achieving and maintaining a minimum of 85% vegetative cover using an erosion control seed mix, whether applied in a blanket or otherwise, that is certified by its manufacturer as not containing any invasive species; or placing and maintaining a minimum of 3 inches of non-erosive material such as stone.
9. In accordance with Env-Wt 307.03(d), any sediment collected by water quality control measures shall be removed with sufficient frequency to prevent the discharge of sediment; and placed in an upland location in a manner that prevents its erosion into a surface water or wetland.
10. In accordance with Env-Wt 307.03(c)(7), temporary water quality control methods shall be removed upon completion of work when compliance with Env-Wt 307.03(c)(6) is achieved.
11. In accordance with Env-Wt 307.03(h), equipment shall be staged and refueled outside of jurisdictional areas (unless allowed) and in accordance with Env-Wt 307.15.
12. All dredging activities shall meet all of the conditions listed in Rule Env-Wt 307.10(a) through (n).
13. In accordance with Env-Wt 307.05(e), to prevent the use of soil or seed stock containing nuisance or invasive species, the contractor responsible for work shall follow Best Management Practices for the Control of Invasive and Noxious Plant Species (Invasive Plant BMPs).
14. Restoration of all temporary impacts shall meet all of the conditions listed in Rule Env-Wt 307.12(a) through (i).
15. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
16. In accordance with Env-Wt 307.12(i), wetland areas where permanent impacts are not authorized shall be restored to their pre-impact conditions and elevation by replacing the removed soil and vegetation in their pre-construction location and elevation such that post-construction soil layering and vegetation schemes are as close as practicable to pre-construction conditions.
17. In accordance with Env-Wt 307.12(a), within 3 days of final grading or temporary suspension of work in an area that is in or adjacent to surface waters, all exposed soil areas shall be stabilized by seeding and mulching, if during the growing season; or mulching with tackifiers on slopes less than 3:1 or netting and pinning on slopes steeper than 3:1 if not within the growing season.
18. In accordance with Env-Wt 307.03(g)(1), the person in charge of construction equipment shall inspect such equipment for leaking fuel, oil, and hydraulic fluid each day prior to entering surface waters or wetlands or operating in an area where such fluids could reach groundwater, surface waters, or wetlands.
19. In accordance with Env-Wt 307.03(g)(2), the person in charge of construction equipment shall repair any leaks prior to using the equipment in an area where such fluids could reach groundwater, surface waters, or wetlands.
20. In accordance with Env-Wt 307.03(g)(3) and (4), the person in charge of construction equipment shall maintain oil spill kits and diesel fuel spill kits, as applicable to the type(s) and amount(s) of oil and diesel fuel used, on site so as to be readily accessible at all times during construction; and train each equipment operator in the use of the spill kits.
21. In accordance with Env-Wt 307.03(e), all exposed soils and other fills shall be permanently stabilized within 3 days following final grading.

**GENERAL CONDITIONS THAT APPLY TO ALL NHDES WETLANDS PERMITS:**

1. Pursuant to RSA 482-A:12, a copy of the permit shall be posted in a secure manner in a prominent place at the site of the approved project.
2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
3. In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee and the principal contractor who will build or install the project prior to start of construction; and will not be valid until signed.

4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under the permit.
5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by the permit.
6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to and approval by NHDES.
7. In accordance with Env-Wt 307.02, in order to be in compliance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (US ACE) shall comply with all conditions of the applicable state general permit (see attached notice).
8. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or designated or proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A. A copy of this permit shall be posted on site during construction in a prominent location visible to inspecting personnel.

APPROVED:



Karl Benedict  
Land Resources Management, Water Division

=====

**BY SIGNING BELOW, I HEREBY CERTIFY THAT I HAVE FULLY READ THIS PERMIT AND AGREE TO ABIDE BY ALL PERMIT CONDITIONS.**

\_\_\_\_\_  
OWNER'S SIGNATURE (required)

\_\_\_\_\_  
CONTRACTOR'S SIGNATURE (required)

